SUPPORT

TOTALLY INTERNALLY FLANGED (TIF) c/w SELF-DRAINING EXTERNALLY FLANGED BASE Tank Support & Clearance Requirements

Surface variation not more than 2mm in

1m AND no more than 6mm in 6m

Secondary support

Shims not exceeding 18mm



An Externally Flanged Base tank must be placed on either support walls, steelwork or a combination of both. The top surface of which should be flat, level and free from any local irregularities and should not vary more than 2mm in any 1m or a total of 6mm in any 6m, measured laterally or diagonally.

The completed base structure shall be capable of supporting the weight of the tank and its maximum water load i.e. filled to the brim, along with any potential wind or snow loads as applicable.

If foundations are to be provided by suspended floors or beams, then the foundation should be constructed so that when the tank is full, the combined deflections should not exceed 1/500th of the span (BS EN 13280:2001).

Primary support

Alternatively, if the pier tolerance cannot be achieved, the use of levelling steels will allow you take up any irregularities with shims up to a maximum of 18mm. Our standard levelling steels are 100mm x 50mm high galvanised box section and are non-spanning. These arrangements are only suitable for tank heights up to 2m and require pier centres of 1m.

DELIVER'

Tanks with more than one 0.5m lateral dimension will require secondary steel supports at 500mm centres to run perpendicular to the primary supports (min 500mm high).

The size of the secondary steels will depend on the spanning distance, please contact us for further guidance. Shims not exceeding 18mm

Secondary Support @ 500mm centres

Primary support @ no less than 1m centres

IN 1956

TECH

CERTIFIED

Approved



Primary support

REGULATION 4

CLEARANCE

CLEARANCE REQUIREMENTS.


For Installation and Future Maintenance



Email: websales@tricelpumps.co.uk

This style of tank is ideal where space is limited and can be pushed within 50mm of a wall.

The minimum learance requirements taken from the external measurements of the tank are 50mm on 3 sides, minimum 500mm (*1000mm when fitted with a hooped ladder) on the 4th side to accommodate pipework and 750mm headroom clearance for safe access (**1200mm when fitted with Guardrail).



TRICEL LANARK

Riverside Road, Kirkfieldbank, Lanark, ML11 9JS, United Kingdom. Tel: +44 (0) 1555 700620 Email: lanark@tricelwater.co.uk

Winterstoke Road, Weston-super-Mare, Email: weston@tricelwater.co.uk

Tel: +44 (0) 208 103 6056 Email: croydon@tricelwater.co.uk